LEADERS LINE
TRADING LLC

SECURITY | IOT | AUTOMATION | SOLUTIONS

TRN 100362683300003

M05, Al Nisf, Airport Road
Dubai, UAE

www.llct.net · www.o2iot.ae

QUOTATION

THANK YOU FOR YOUR ENQUIRY

QTN231026418

PREPARED FOR

Client (to be confirmed)

DATE	23 Oct 2026
VALID UNTIL	07 Nov 2026
CONTACT	Anwar
MOBILE / EMAIL	+971 50 803 1282 | anwar@llct.net
SALESPERSON	Anwar

SUBJECT *Supply, installation, testing & commissioning of IP CCTV system – 124 cameras, 30 days recording*

#	ITEM & DESCRIPTION	QTY	UNIT	UNIT PRICE (AED)	AMOUNT (AED)
01	**Dahua 4MP IR Vandal-proof Dome IP Camera** Model DH-IPC-HDBW2441E-S · WizSense, 2.8 mm, IR 30 m, H.265+, IK10, IP67, PoE · indoor areas	84	pcs	265.00	**22,260.00**
02	**Dahua 4MP IR Bullet IP Camera** Model DH-IPC-HFW2441S-S · WizSense, 2.8 mm, IR 30 m, H.265+, IP67, PoE · outdoor / perimeter	40	pcs	270.00	**10,800.00**
03	**Camera Back Box / Junction Box** Dahua aluminium junction box (IP66) matched to each camera model, for neat cable entry and mounting	124	pcs	45.00	**5,580.00**
04	**Dahua 32-Channel AI NVR** Model NVR5432-EI · 32 ch, 4 SATA bays, 4K HDMI output, WizSense AI search, H.265+ · 4 units = 128 channels (124 cameras + 4 spare)	4	pcs	2,950.00	**11,800.00**
05	**Seagate SkyHawk 8TB Surveillance HDD** 3.5" SATA, 24/7 rated · 3 per NVR = 24 TB per NVR for 30 days continuous recording (31 cameras × ~650 GB each, 4MP H.265 @ 2 Mbps)	12	pcs	850.00	**10,200.00**
06	**Display 43" 4K UHD Monitor** 43" 4K LED display for live view in security room, with wall bracket and 5 m HDMI cable	1	pcs	1,350.00	**1,350.00**
07	**D-Link 24-port Gigabit PoE Smart Managed Switch** Model DGS-1210-28P · 24 × GE PoE (193 W budget) + 4 SFP/combo, rack mount · 6 units = 144 PoE ports for 124 cameras	6	pcs	1,750.00	**10,500.00**
08	**D-Link 24-port Gigabit Smart Managed Core Switch** Model DGS-1210-28 · 24 × GE + 4 SFP · aggregates PoE switches and NVRs, terminates fibre uplink	1	pcs	950.00	**950.00**
09	**1G Single-mode SFP Module (LX, 10 km)** D-Link DEM-310GT, LC duplex · one at each end of the fibre uplink	2	pcs	260.00	**520.00**

#	ITEM & DESCRIPTION	QTY	UNIT	UNIT PRICE (AED)	AMOUNT (AED)
10	**Fibre Optic Cable 6-core Single-mode Armoured** OS2, outdoor/indoor armoured, for uplink from CCTV rack to main network room (estimated 200 m)	200	m	7.00	**1,400.00**
11	**Fibre Patch Panel (LIU) 12-port, Rack-mount** 1U sliding LIU with LC adapters, splice tray and SM pigtails · one at each end	2	pcs	480.00	**960.00**
12	**LC-LC Single-mode Duplex Patch Cord 3 m** OS2 fibre patch cords for SFP connection	2	pcs	45.00	**90.00**
13	**Fibre Splicing & OTDR Testing** Fusion splicing of 6 cores at both ends, OTDR / power-meter test report	1	lot	1,400.00	**1,400.00**
14	**42U Floor-standing Network Rack 800 × 1000** 800 W × 1000 D, perforated front & rear doors, side panels, 4 roof fans, 2 fixed shelves, castors & levelling feet, earthing kit	1	pcs	3,200.00	**3,200.00**
15	**PDU 12-way Rack-mount** 19" universal sockets with surge protection and switch	2	pcs	280.00	**560.00**
16	**1U Horizontal Cable Manager** Metal, with D-rings, for neat patching	7	pcs	65.00	**455.00**
17	**24-port Cat6 Patch Panel (loaded)** 1U, 19", with rear cable management · 6 panels = 144 ports	6	pcs	360.00	**2,160.00**
18	**Cat6 Patch Cord 1 m** Moulded boots · camera ports, switch uplinks and NVR connections	140	pcs	9.00	**1,260.00**
19	**APC Smart-UPS 3 kVA Rack-mount** Model SMT3000RMI2UC · 3000 VA / 2700 W, pure sine wave, LCD · backup for switches, NVRs and monitor (≈1.3 kW load)	1	pcs	2,650.00	**2,650.00**
20	**Cat6 U/UTP LSZH Cable 305 m (Schneider Actassi)** 23 AWG solid copper, LSZH · 124 points × avg 50 m + 5% wastage ≈ 6510 m	22	box	690.00	**15,180.00**
21	**RJ45 Cat6 Connectors with Boots (100 pcs)** Camera-end termination	3	box	65.00	**195.00**
22	**GI Cable Tray / Trunking 100 × 50 mm with Cover** Main cable route with couplers, bends, tees, hangers and supports (estimated 300 m)	300	m	38.00	**11,400.00**
23	**PVC Heavy-gauge Conduit 20 mm with Fittings** Drops from main route to each camera (avg 15 m per point) incl. saddles, bends, couplers and junction boxes	1860	m	6.00	**11,160.00**
24	**Flexible Conduit 20 mm with Glands** Final connection into each camera back box (1.5 m per point)	186	m	5.00	**930.00**
25	**Installation of Containment** Fixing of cable tray/trunking and conduit system as per route plan, incl. fixings and supports	1	lot	22,380.00	**22,380.00**
26	**Cable Pulling, Termination & Testing** Per point: pull Cat6 through containment, terminate RJ45 at camera and patch panel at rack, label both ends, continuity / Fluke test	124	point	85.00	**10,540.00**
27	**Camera Installation & Alignment** Per camera: mount back box and camera, focus and angle adjustment to agreed field of view	124	pcs	75.00	**9,300.00**

#	ITEM & DESCRIPTION	QTY	UNIT	UNIT PRICE (AED)	AMOUNT (AED)
28	**Fibre Cable Laying** Pull and fix 6-core armoured fibre in containment between CCTV rack and network room	200	m	8.00	**1,600.00**
29	**Rack Assembly, NVR & Network Configuration** Rack build, UPS/PDU, switches (VLAN, PoE, uplink), NVR setup, HDD format, recording schedule, AI rules, user accounts, DMSS mobile & SmartPSS remote viewing	1	lot	4,500.00	**4,500.00**
30	**Testing, Commissioning & Handover** End-to-end test, 30-day retention check, user training, camera schedule, as-built drawings and handover documents	1	lot	3,500.00	**3,500.00**
31	**Access Equipment & Consumables** Ladders / mobile scaffold, cable ties, labels, sleeves, fixings and site consumables	1	lot	2,000.00	**2,000.00**

NOTES

Design basis: 84 dome + 40 bullet Dahua 4MP WizSense cameras; 4 × 32-ch NVR (31 cameras each); 30 days continuous recording at 4MP H.265, 20 fps (~2 Mbps per camera ≈ 650 GB per camera per month) on 3 × 8 TB per NVR; all cameras home-run on Cat6 to one 42U rack (max 90 m per run); one single-mode fibre uplink to the client network. Quantities of cable and containment are estimates and will be measured on site.

AMOUNT IN WORDS

One hundred and eighty-nine thousand eight hundred and nineteen dirhams only

SUBTOTAL	180,780.00
VAT 5%	9,039.00
TOTAL AED	**189,819.00**

TERMS & CONDITIONS

1. Prices are valid for 15 days from the quotation date.
2. Payment: 50% advance with LPO, 40% on delivery of materials, 10% on testing & commissioning.
3. Delivery: 2–3 weeks for materials from LPO; installation 3–4 weeks depending on site access.
4. Warranty: 2 years on Dahua equipment (manufacturer), 1 year on workmanship.
5. Exclusions: civil works, core drilling, false-ceiling opening/closing, power points, fire-stopping, permits and internet connection.
6. Cable and containment lengths are estimates; final quantities will be measured and billed as installed.

BANK DETAILS

Account name LEADERS LINE TRADING LLC

WIO Bank, Dubai · IBAN AE250860000009674830642

RAK Bank (Amal), Dubai · Account 8882060635901 · IBAN AE510400008882060635901

For LEADERS LINE TRADING LLC
Authorised signatory

Accepted by
Name, signature, company stamp & date