# LEADERS LINE
TRADING LLC

SECURITY | IOT | AUTOMATION | SOLUTIONS

TRN 100362683300003

M05, Al Nisf, Airport Road
Dubai, UAE

www.llct.net · www.o2iot.ae


# QUOTATION

THANK YOU FOR YOUR ENQUIRY

QTN231026418

PREPARED FOR

**Client (to be confirmed)**

| | |
|---|---|
| DATE | 23 Oct 2026 |
| VALID UNTIL | 07 Nov 2026 |
| CONTACT | Anwar |
| MOBILE / EMAIL | +971 50 803 1282 \| anwar@llct.net |
| SALESPERSON | Anwar |

SUBJECT *Supply, installation, testing & commissioning of IP CCTV system – 124 cameras, 30 days recording*

| # | ITEM & DESCRIPTION | QTY | UNIT | UNIT PRICE (AED) | AMOUNT (AED) |
|---|---|---|---|---|---|
| 01 | **Dahua 4MP IR Vandal-proof Dome IP Camera**<br>Model DH-IPC-HDBW2441E-S · WizSense, 2.8 mm, IR 30 m, H.265+, IK10, IP67, PoE · indoor areas | 84 | pcs | 265.00 | **22,260.00** |
| 02 | **Dahua 4MP IR Bullet IP Camera**<br>Model DH-IPC-HFW2441S-S · WizSense, 2.8 mm, IR 30 m, H.265+, IP67, PoE · outdoor / perimeter | 40 | pcs | 270.00 | **10,800.00** |
| 03 | **Camera Back Box / Junction Box**<br>Dahua aluminium junction box (IP66) matched to each camera model, for neat cable entry and mounting | 124 | pcs | 45.00 | **5,580.00** |
| 04 | **Dahua 32-Channel AI NVR**<br>Model NVR5432-EI · 32 ch, 4 SATA bays, 4K HDMI output, WizSense AI search, H.265+ · 4 units = 128 channels (124 cameras + 4 spare) | 4 | pcs | 2,950.00 | **11,800.00** |
| 05 | **Seagate SkyHawk 8TB Surveillance HDD**<br>3.5" SATA, 24/7 rated · 3 per NVR = 24 TB per NVR for 30 days continuous recording (31 cameras × ~650 GB each, 4MP H.265 @ 2 Mbps) | 12 | pcs | 850.00 | **10,200.00** |
| 06 | **Display 43" 4K UHD Monitor**<br>43" 4K LED display for live view in security room, with wall bracket and 5 m HDMI cable | 1 | pcs | 1,350.00 | **1,350.00** |
| 07 | **D-Link 24-port Gigabit PoE Smart Managed Switch**<br>Model DGS-1210-28P · 24 × GE PoE (193 W budget) + 4 SFP/combo, rack mount · 6 units = 144 PoE ports for 124 cameras | 6 | pcs | 1,750.00 | **10,500.00** |
| 08 | **D-Link 24-port Gigabit Smart Managed Core Switch**<br>Model DGS-1210-28 · 24 × GE + 4 SFP · aggregates PoE switches and NVRs, terminates fibre uplink | 1 | pcs | 950.00 | **950.00** |
| 09 | **1G Single-mode SFP Module (LX, 10 km)**<br>D-Link DEM-310GT, LC duplex · one at each end of the fibre uplink | 2 | pcs | 260.00 | **520.00** |

| # | ITEM & DESCRIPTION | QTY | UNIT | UNIT PRICE (AED) | AMOUNT (AED) |
|---|---|---|---|---|---|
| 10 | **Fibre Optic Cable 6-core Single-mode Armoured**<br>OS2, outdoor/indoor armoured, for uplink from CCTV rack to main network room (estimated 200 m) | 200 | m | 7.00 | **1,400.00** |
| 11 | **Fibre Patch Panel (LIU) 12-port, Rack-mount**<br>1U sliding LIU with LC adapters, splice tray and SM pigtails · one at each end | 2 | pcs | 480.00 | **960.00** |
| 12 | **LC-LC Single-mode Duplex Patch Cord 3 m**<br>OS2 fibre patch cords for SFP connection | 2 | pcs | 45.00 | **90.00** |
| 13 | **Fibre Splicing & OTDR Testing**<br>Fusion splicing of 6 cores at both ends, OTDR / power-meter test report | 1 | lot | 1,400.00 | **1,400.00** |
| 14 | **42U Floor-standing Network Rack 800 × 1000**<br>800 W × 1000 D, perforated front & rear doors, side panels, 4 roof fans, 2 fixed shelves, castors & levelling feet, earthing kit | 1 | pcs | 3,200.00 | **3,200.00** |
| 15 | **PDU 12-way Rack-mount**<br>19" universal sockets with surge protection and switch | 2 | pcs | 280.00 | **560.00** |
| 16 | **1U Horizontal Cable Manager**<br>Metal, with D-rings, for neat patching | 7 | pcs | 65.00 | **455.00** |
| 17 | **24-port Cat6 Patch Panel (loaded)**<br>1U, 19", with rear cable management · 6 panels = 144 ports | 6 | pcs | 360.00 | **2,160.00** |
| 18 | **Cat6 Patch Cord 1 m**<br>Moulded boots · camera ports, switch uplinks and NVR connections | 140 | pcs | 9.00 | **1,260.00** |
| 19 | **APC Smart-UPS 3 kVA Rack-mount**<br>Model SMT3000RMI2UC · 3000 VA / 2700 W, pure sine wave, LCD · backup for switches, NVRs and monitor (≈1.3 kW load) | 1 | pcs | 2,650.00 | **2,650.00** |
| 20 | **Cat6 U/UTP LSZH Cable 305 m (Schneider Actassi)**<br>23 AWG solid copper, LSZH · 124 points × avg 50 m + 5% wastage ≈ 6510 m | 22 | box | 690.00 | **15,180.00** |
| 21 | **RJ45 Cat6 Connectors with Boots (100 pcs)**<br>Camera-end termination | 3 | box | 65.00 | **195.00** |
| 22 | **GI Cable Tray / Trunking 100 × 50 mm with Cover**<br>Main cable route with couplers, bends, tees, hangers and supports (estimated 300 m) | 300 | m | 38.00 | **11,400.00** |
| 23 | **PVC Heavy-gauge Conduit 20 mm with Fittings**<br>Drops from main route to each camera (avg 15 m per point) incl. saddles, bends, couplers and junction boxes | 1860 | m | 6.00 | **11,160.00** |
| 24 | **Flexible Conduit 20 mm with Glands**<br>Final connection into each camera back box (1.5 m per point) | 186 | m | 5.00 | **930.00** |
| 25 | **Installation of Containment**<br>Fixing of cable tray/trunking and conduit system as per route plan, incl. fixings and supports | 1 | lot | 22,380.00 | **22,380.00** |
| 26 | **Cable Pulling, Termination & Testing**<br>Per point: pull Cat6 through containment, terminate RJ45 at camera and patch panel at rack, label both ends, continuity / Fluke test | 124 | point | 85.00 | **10,540.00** |
| 27 | **Camera Installation & Alignment**<br>Per camera: mount back box and camera, focus and angle adjustment to agreed field of view | 124 | pcs | 75.00 | **9,300.00** |

| # | ITEM & DESCRIPTION | QTY | UNIT | UNIT PRICE (AED) | AMOUNT (AED) |
|---|---|---|---|---|---|
| 28 | **Fibre Cable Laying**<br>Pull and fix 6-core armoured fibre in containment between CCTV rack and network room | 200 | m | 8.00 | **1,600.00** |
| 29 | **Rack Assembly, NVR & Network Configuration**<br>Rack build, UPS/PDU, switches (VLAN, PoE, uplink), NVR setup, HDD format, recording schedule, AI rules, user accounts, DMSS mobile & SmartPSS remote viewing | 1 | lot | 4,500.00 | **4,500.00** |
| 30 | **Testing, Commissioning & Handover**<br>End-to-end test, 30-day retention check, user training, camera schedule, as-built drawings and handover documents | 1 | lot | 3,500.00 | **3,500.00** |
| 31 | **Access Equipment & Consumables**<br>Ladders / mobile scaffold, cable ties, labels, sleeves, fixings and site consumables | 1 | lot | 2,000.00 | **2,000.00** |

## NOTES

Design basis: 84 dome + 40 bullet Dahua 4MP WizSense cameras; 4 × 32-ch NVR (31 cameras each); 30 days continuous recording at 4MP H.265, 20 fps (~2 Mbps per camera ≈ 650 GB per camera per month) on 3 × 8 TB per NVR; all cameras home-run on Cat6 to one 42U rack (max 90 m per run); one single-mode fibre uplink to the client network. Quantities of cable and containment are estimates and will be measured on site.

AMOUNT IN WORDS

**One hundred and eighty-nine thousand eight hundred and nineteen dirhams only**

| | |
|---|---|
| SUBTOTAL | 180,780.00 |
| VAT 5% | 9,039.00 |
| **TOTAL AED** | **189,819.00** |

## TERMS & CONDITIONS

1. Prices are valid for 15 days from the quotation date.
2. Payment: 50% advance with LPO, 40% on delivery of materials, 10% on testing & commissioning.
3. Delivery: 2–3 weeks for materials from LPO; installation 3–4 weeks depending on site access.
4. Warranty: 2 years on Dahua equipment (manufacturer), 1 year on workmanship.
5. Exclusions: civil works, core drilling, false-ceiling opening/closing, power points, fire-stopping, permits and internet connection.
6. Cable and containment lengths are estimates; final quantities will be measured and billed as installed.

**For LEADERS LINE TRADING LLC**
Authorised signatory

**Accepted by**
Name, signature, company stamp & date